

1 LEVEL 2, WING C: ELECTRICAL DEMOLITION PLAN

SCALE: 1/8" = 1'-0"

KEYED DEMOLITION NOTES:

- (1) THE ELECTRICAL CONTRACTOR SHALL TAKE DOWN AND PUT BACK ALL CEILING MOUNTED LIGHT FIXTURES, SPEAKERS, FIRE ALARM DEVICES, AND ANY OTHER ELECTRICAL-RELATED CEILING MOUNTED DEVICE OR EQUIPMENT AS REQUIRED TO ACCOMMODATE HVAC RENOVATION WORK. DISCONNECT, REMOVE, AND STORE ALL MATERIAL IN A SAFE PLACE AS DESIGNATED BY THE VA. UPON COMPLETION OF HVAC RENOVATION WORK, REINSTALL AND RECONNECT FIXTURES AND DEVICES AS BEFORE AND ASSURE PROPER OPERATION. ALL DISCONNECTED LINE VOLTAGE POWER CONDUCTORS SHALL BE PROPERLY INSULATED AND MADE SAFE. WHERE A FIRE ALARM DEVICE HAS TO BE TEMPORARILY REMOVED FROM THE CEILING TILE, CAREFULLY SUSPEND THE DEVICE FROM THE STRUCTURE ABOVE IN A MANNER IN WHICH IT, AND ASSOCIATED CIRCUITRY, WILL NOT BE DAMAGED DURING HVAC RENOVATION WORK. IF IT IS NECESSARY TO COMPLETELY DISCONNECT AND REMOVE ANY FIRE ALARM DEVICE, THE ASSOCIATED FIRE ALARM CIRCUITRY MUST BE TEMPORARILY RECONNECTED IN SUCH A WAY AS TO MAINTAIN CIRCUIT CONTINUITY AND FUNCTIONALITY OF OTHER EXISTING FIRE ALARM DEVICES ON THAT CIRCUIT. IT SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR TO REPAIR OR REPLACE TO THE VA'S SATISFACTION ANY FIXTURES OR DEVICES THAT BECOME DAMAGED DURING AND AS A RESULT OF THIS PROCESS.
- (2) REMOVE EXISTING 32W T8 LAMPS FROM ALL FIXTURES SHOWN ON THIS DRAWING AND REPLACE WITH NEW ENERGY SAVING LAMPS AS SPECIFIED ON THE RENOVATION PLAN ON SHEET EP1.0.

GENERAL NOTES:

1. THE ELECTRICAL CONTRACTOR SHALL CAREFULLY REVIEW THE MECHANICAL DEMOLITION PLANS IN ORDER TO UNDERSTAND THE EXTENT OF WORK TO BE EXECUTED ABOVE THE VARIOUS CEILING, WHICH IN TURN WILL HELP DETERMINE THE EXTENT OF CEILING MOUNTED ELECTRICAL DEVICES (LIGHT FIXTURES, SPEAKERS, FIRE ALARM DEVICES, POWER POLES, ETC.) THAT WILL BE REQUIRED TO BE DISCONNECTED AND REMOVED TO ACCOMMODATE MECHANICAL WORK AND RE-INSTALLED AND RE-CONNECTED ONCE WORK IS COMPLETE. THE ELECTRICAL CONTRACTOR SHALL CLOSELY COORDINATE WITH THE MECHANICAL CONTRACTOR.
2. ALL LINE VOLTAGE BRANCH CIRCUITS DISCONNECTED SHALL BE MADE SAFE DURING THIS WORK. WHERE POSSIBLE, SERVING CIRCUIT BREAKERS SHALL BE LOCKED OUT/TAGGED OUT. EXPOSED CONDUCTOR ENDS SHALL BE PROPERLY INSULATED AND TIED BACK/SUPPORTED AS REQUIRED.
3. COORDINATE ALL WORK AND OUTAGES WITH THE MECHANICAL CONTRACTOR AND THE VA CONTRACTING OFFICER.


ASBESTOS NOTE:
IF THE EXECUTION OF THIS WORK REQUIRES THE DISTURBING OF ANY SUBSTANCE WHICH APPEARS TO BE ASBESTOS OR WHICH MAY CONTAIN ASBESTOS FIBER, NOTIFY THE OWNER BEFORE CONTINUING WORK AT THE SUSPECT LOCATION. ANY MATERIAL TESTING POSITIVE SHALL BE REMOVED BY THE OWNER BEFORE WORK CONTINUES.

NOTE: EXISTING CONDITIONS SHOWN WERE DERIVED FROM OWNER FURNISHED DRAWINGS AND FIELD OBSERVATIONS. SOME BUILDING FEATURES AND MEP SYSTEMS ARE NOT SHOWN FOR CLARITY. FIELD VERIFY BUILDING CONSTRUCTION. FIELD VERIFY THE LOCATION, SIZE AND QUANTITY OF ALL EQUIPMENT.

The seal appearing on this document was authorized by Stanley H. Curtis, 201789 on 8/19/2013. Attention: a sealed document without proper notification to the responsible engineer is an offense under the Oklahoma Engineering Practice Act.



8/19/2013



KEY PLAN
SCALE: NO SCALE
PROJECT NORTH

REVISIONS	DESCRIPTION	DATE



Dept. of Veterans Affairs
Jack C. Montgomery
Medical Center
1011 Honor Height Drive
Muskogee, Oklahoma 74401

ENGINEER:

RMD CONSULTING, LLC
2815 VALLEY VIEW LANE, STE. 214
DALLAS, TX 75234
P: 972-488-8077 F: 972-488-8174
OK REG. ENGINEERING FIRM: 5183

CONSULTANTS:

ARCHITECT:
ARCHITECTURAL CONCEPTS, INC.
669 AIRPORT FREEWAY, STE. 300
HURST, TX 76053
P: 817-285-8885 F: 817-285-8021

APPROVED:	APPROVED: Interior Designer
APPROVED:	APPROVED:
APPROVED:	APPROVED:
APPROVED:	APPROVED:

APPROVED: Safety Manager
APPROVED: Infection Control Nurse
APPROVED: Industrial Hygienist
APPROVED: President A.F.G.E. 2250

APPROVED: Medical Center Director
APPROVED: Associate Director
APPROVED: Chief of Staff
APPROVED: Chief of Engineering Service

DRAWING TITLE LEVEL 2, WING C: ELECTRICAL DEMOLITION PLAN
PROJECT NO. 623-11-107
BUILDING NO. CLINICAL

CONTRACT NO. VA256-12-C-0295
AUTOCAD FILE NAME:

PROJECT TITLE REPLACE LABORATORY AIR HANDLING UNITS
DESIGNED BY: TGB
DRAWN BY: TGB
CHECKED BY: SRC

LOCATION Jack C. Montgomery VA Medical Center
--

DATE 8/19/2013
SCALE AS SHOWN
DRAWING NO. ED1.0
DWG. 29 OF 40

DEPARTMENT OF
VETERANS AFFAIRS